ADMIN-BAC FORM1-10
Rev. 2, January 1, 2024

Standard Form Number: **SF-GOOD-60**
Revised on May 24, 2004

Republic of the Philippines
Government of Ormoc City
BIDS AND AWARDS COMMITTEE
Ormoc City

ORWASA
P.R. No.: **240719**
Quotation No.: **243269-1925**
PhilGEPs No.:

Standard Form Title:

REQUEST FOR QUOTATION

Please quote your lowest price on the item/s listed below, subject to the General Conditions on the last page, stating the shortest time of delivery and submit your quotation duly signed by you or your authorized representative not later than _____ _____.

LOUCELLE MAE B. ARANETA
PROCUREMENT OFFICER

NOTE: **(1)** ALL ENTRIES MUST BE TYPEWRITTEN OR LEGIBLY WRITTEN. (2) DELIVERY PERIOD WITHIN 30 C.D. UPON RECEIPT OF THE APPROVED FUNDED PURCHASE ORDER (P.O.). Administrative penalties pursuant to Sec. 69 of the Revised IRR-RA 9184 shall be for a minimum for non-delivery without valid reason. **(3)** WARRANTY SHALL BE FOR A PERIOD OF THREE (3) MONTHS OF SUPPLIES & MATERIALS, ONE (1) YEAR FOR EQUIPMENT, FROM DATE OF ACCEPTANCE BY THE END-USER. **(4)** PRICE VALIDITY SHALL BE FOR A PERIOD OF SIXTY (60) DAYS. (5) G-EPS REG NO., MAYORs PERMIT, DTI/SEC, AND FOR ABC's ABOVE 500K - ITR & OMNIBUS SWORN STATEMENT SHALL BE ATTACHED UPON SUBMISSION **(6)** BIDDERS SHALL SUBMIT ORIGINAL BROCHURES SHOWING CERTIFICATIONS OF THE PRODUCTS IF APPLICABLE. **(7)** THE ***APPROVED BUDGET CEILING*** FOR THIS PROCUREMENT IS (amount indicated below)

Php ***892,386.00***

	Activities	Schedule	
		FROM	TO
1	Issuance of Canvass	***Tuesday February 20, 2024***	***Friday February 23, 2024***
2	Submission of Canvass	***Monday February 26, 2024***	***10:00 AM***
3	Opening of Canvass	***Monday February 26, 2024***	***2:00 PM***

#	Item and Description	QTY	UNIT COST	TOTAL
1	*Transformer*	*9 unit*		
	15 KVA Transformer, 1 - phase, oil immered, 2-2.5%			
	external tap changer including fuse cut-out & ligthning			
	arrester			
	Specification:			
	Primary voltage 13200/7620 Volts			
	Secondary Voltage 240/120 volts			
	Core loss = 50 watts			
	Copper loss = 195 watts			
	% impedance 2			
	Double primary bushing			
	Polarity additive			
	Note:			
	Required to submit transformers test result of each			
	transformer. Transformer test must be conducted by Leyeco			
	V electric cooperative.			
	-x-x-x-x-x-x-x- NOTHING FOLLOWS -x-x-x-x-x-x-x-			
			GRAND TOTAL >>>	

*

Brand and Model : _____ *Warranty :* _____
Delivery Period : _____ *Price Validity :* _____

After having carefully read and accepted your Conditions, I/We quote you on the item at prices noted above and hereby commit to deliver the same if adjudged to have the lowest and responsive quotation.

_____
Business Name

_____
Printed Name/Signature/Date